

SCADA and Control Requirements

WRIG March 2021

Agenda

1. Proposed Operational Data Points Technical Specification for new Facilities
2. Proposed operation of Look Ahead points and Fast Start Facility considerations

Technical Specification: Operational Data Points for Generating Facilities - Scheduled

- AEMO will shortly circulate a draft of the new Technical Specification.
- This document provides guidance on the requirements for new facilities seeking to participate in the WEM.
- Includes AEMO's proposed requirements for grid-scale Electric Storage Resources (e.g. batteries).
- Includes updates for requirements for other technology types.
- May require additional specific points depending on site specifics (e.g. special protection schemes)
- As new technologies mature, AEMO will continue to review and update.
- AEMO seeks feedback on the content and usefulness of this document.

Technical Specification: Operational Data Points for Generating Facilities – Semi-Scheduled and Non-Scheduled


- No change for existing Intermittent Non-Scheduled Generators that are automatically dispatched and have overall Facility MW and ramp rate setpoints.
- Facilities that do not have automated setpoint control will need to have these installed if they are classified as a Semi-Scheduled Facility.
- Smaller Facilities (<10 MW) are likely to be classified as Non-Scheduled Facilities. These Facilities do not need to receive automated setpoints, but do need to be able to respond to AEMO directions (via phone).

Look Ahead Points

- A number of facilities currently operate with Look-Ahead points that receive indicative Dispatch Targets at fixed periods ahead of real-time.
- Proposal that Look-Ahead 1 (currently fixed at +5 minutes for all participants) becomes the Dispatch Target (EOI) value in the new market.
- For a facility with existing Look-Ahead points more than 5 minutes ahead, AEMO can feed Dispatch Schedule forecasts to these points.
 - Only provided at the Dispatch Schedule granularity (5 minutes).
- Facilities will need to consider implications for their future operation.

Example: Changes to Lookahead Signals

Current Market



Facility moving from 100MW to 110MW and then 120MW.


Desired MW = Current Dispatch Target (EOI)

Lookahead 1 = + 5 minutes

Lookahead 2 = +15 minutes

Lookahead 3 = +30 minutes

New Market



Facility moving from 100MW to 110MW and then 120MW.

Desired MW = Linear Dispatch Target
Lookahead 1 = Current Dispatch Target
Lookahead 2 = +15 minutes
Lookahead 3 = +30 minutes

Fast Start Operation and Look Ahead Points

- If a Facility wishes to participate as a Fast Start Facility, it will need a SCADA point for AEMO to send indications of a start to.
- This could be:
 - An existing or new digital start control;
 - An existing or new analogue point, with an agreed value to indicate start/stop
- AEMO can facilitate both approaches.
- Participants will need to consider facility logic in response to Look Ahead signals while bid as a Fast Start Facility.
 - If a Facility wishes to enable logic to automate its start based on look-ahead signals, it will need to rebid not using a FSIP, and manage its own start.
- AEMO seeks feedback from Participants who have Facilities that they wish to operate as Fast Start Facilities on:
 - How they wish for Fast Start signals to be communicated to their facilities;
 - How these fast start signals may interact with existing facility logic; and
 - Any other matters of concerns or any clarifications sought in relation to this topic.

Example 1: Self-Commitment Operation

12:00 WEMDE Run

Item	12:05	12:10	12:15 – LA2	12:20
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	0 MW	0 MW	15 MW
FSIP Mode	N/A	-	-	-
Facility Status	Ready to Start			

- Facility forecast to receive a dispatch target at 12:15 for 12:20 based on current Pre-Dispatch
- Facility has 15 minute sync time. This is linked to the Look-Ahead 2 point (LA2), which is fed the results of the 15 minute ahead Pre-Dispatch outcomes.
- At 12:00, 15 minutes ahead is still forecast for 0 MW Dispatch Target, and so no action is taken.

12:05 WEMDE Run

Item	12:10	12:15	12:20 - LA2	12:25
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	0 MW	15 MW	20 MW
FSIP Mode	N/A	-	-	-
Facility Status	Start initiated			

- At 12:05, the PD results are updated for 12:20, indicating a 15 MW target. The Facility has chosen to implement automated logic to start at this point.
- The Participant should re-bid the Facility to ensure it is clearing for the appropriate quantity for the 12:20-12:25 Dispatch Interval at this point.

12:10 WEMDE Run

Item	12:15	12:20	12:25 - LA2	12:30
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	15 MW	20 MW	20 MW
FSIP Mode	N/A	-	-	-
Facility Status	Start in Progress			

- Facility is in the process of starting.
- Note, the 12:20 Pre-Dispatch will only indicate a dispatch if the facility has rebid as "In-Service" for this interval. If the Facility is still bid as "Available", this value will be zero, as it will not be considered for dispatch within its start time.

12:15 WEMDE Run

Item	12:20	12:25	12:30 - LA2	12:35
Dispatch Target	15 MW	-	-	-
Pre-Dispatch indicative target	-	15 MW	20 MW	30 MW
FSIP Mode	N/A	-	-	-
Facility Status	Synchronised			

- Facility synchronises at 12:15, and aims to hit its first Dispatch Target of 15 MW on a linear trajectory at 12:20.

Example 2: Fast Start Operation

12:00 WEMDE Run

Item	12:05	12:10	12:15 – LA2	12:20
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	0 MW	0 MW	15 MW
FSIP Mode	0	-	-	-
Facility Status	Ready to Start			

- Facility forecast to receive a dispatch target at 12:15 for 12:20 based on current Pre-Dispatch
- Facility has 15 minute sync time. The Look-Ahead 2 point (LA2), which is fed the results of the 15 minute ahead Pre-Dispatch outcomes.
- At 12:00, 15 minutes ahead is still forecast for 0 MW Dispatch Target, and so no action is taken.

12:05 WEMDE Run

Item	12:10	12:15	12:20 - LA2	12:25
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	0 MW	15 MW	20 MW
FSIP Mode	0	-	-	-
Facility Status	Ready To Start			

- At 12:05, the PD results are updated for 12:20, indicating a 15 MW target. The Facility has chosen not to implement automated start logic in this instance, and so does not respond to this signal.

12:10 WEMDE Run

Item	12:15	12:20	12:25 - LA2	12:30
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	15 MW	20 MW	20 MW
FSIP Mode	0	-	-	-
Facility Status	Ready to Start			

- As per previous run.
- Note that as Facility is offered as FS, and therefore as "In-Service". This means that the 12:20 Pre-Dispatch is continuing to indicate the likely dispatch target, as the offer is not filtered.

12:15 WEMDE Run

Item	12:20	12:25	12:30 - LA2	12:35
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	15 MW	20 MW	30 MW
FSIP Mode	1	-	-	-
Facility Status	Start initiated			

- At 12:15, the WEMDE first pass run would have dispatched this Facility for 15 MW. However, as it was enabled for Fast Start, the second pass run clamps it to 0 MW and initiates a start, dispatching the 15 MW elsewhere for this interval.

12:20 WEMDE Run

Item	12:25	12:30	12:35 - LA2	12:40
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	20 MW	30 MW	30 MW
FSIP Mode	1	-	-	-
Facility Status	Start in Progress			

- As the Facility is still in FS mode 1, it is clamped to zero again.

12:25 WEMDE Run

Item	12:30	12:35	12:40 - LA2	12:45
Dispatch Target	15 MW	-	-	-
Pre-Dispatch indicative target	-	30 MW	30 MW	30 MW
FSIP Mode	2	-	-	-
Facility Status	Synchronised			

- The Facility synchronises, and begins its ramp, moving to FS mode 2.

Example 3: Fast Start Operation in response to a contingency

12:00 WEMDE Run

Item	12:05	12:10	12:15 – LA2	12:20
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	0 MW	0 MW	0 MW
FSIP Mode	0	-	-	-
Facility Status	Ready to Start			

- Facility is not forecast to run under current conditions

12:05 WEMDE Run

Item	12:10	12:15	12:20 - LA2	12:25
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	30 MW	30 MW	35 MW
FSIP Mode	1	-	-	-
Facility Status	Start initiated			

- Just prior to 12:05, a contingency occurs. The constraint / rebid of the tripped unit means that this Facility is now required to operate.
- However, as it is bid as a Fast Start Facility, it's Dispatch Target is clamped to 0 MW, and it is sent a start signal.

12:10 WEMDE Run

Item	12:15	12:20	12:25 - LA2	12:30
Dispatch Target	0 MW	-	-	-
Pre-Dispatch indicative target	-	30 MW	35 MW	40 MW
FSIP Mode	1	-	-	-
Facility Status	Start in Progress			

- Facility is in the process of starting.

12:15 WEMDE Run

Item	12:20	12:25	12:30 - LA2	12:35
Dispatch Target	20 MW	-	-	-
Pre-Dispatch indicative target	-	20 MW	30 MW	30 MW
FSIP Mode	2	-	-	-
Facility Status	Synchronised			

- Facility synchronises at 12:15, and aims to hit its first Dispatch Target of 15 MW on a linear trajectory at 12:20.

Transitional Arrangements

Proposal to support transition

- In order to de-risk cutover and help support both AEMO and participant readiness, AEMO is investigating options for testing/implementing AGC-based balancing earlier
- One proposal is to use the Desired MW to ramp the Facility at the same Ramp Rate as its Dispatch Instruction
- This essentially implements the same control logic as linear ramping, but using the current non-linear ramp rates of the balancing market which means the switchover to SCED becomes much simpler (just a change in ramp-rate and look-ahead 1)
- Potential also to look at moving the LA1 signal early as well
- It would require some transitional rules to support implementing this ahead of market start
- AEMO is seeking feedback from participants on the implications to their site automation or business processes, and whether this could be accommodated ahead of market start

Example

